

Division 05 Structural Steel

Practice file: Cedarline Training Hall, job SYNTH-HALL-01.

Original text. Not a real project and not a platform export.

Section 05 12 00.

Lead time language: mill lead time for structural steel is 8 to 12 weeks after approved shop drawings.

Mill certs: submit mill test reports for steel shapes before erection.

Bolt spec: field bolts are ASTM F3125 Grade A325 unless the drawings say otherwise.

Scope: columns, beams, and the roof joists shown on sheets S-201 and S-202 for this practice hall.

Shop drawings: send erection drawings and piece marks before fabrication. The clock for mill time starts at approval, not at the purchase order.

Coatings: shop primer only. Field paint is Section 09 90 00 and is outside this file.

Tolerances: plumb columns within 1 in 500. Shim with steel plates, not with wood.

Connections: shop welds follow the practice weld procedure WPS-CH-1. Field welds are listed on the piece drawing.

Delivery: tag each piece with the piece mark and the heat number that matches the mill report.

Laydown: the north yard, as the site logistics plan describes. Do not unload onto the south drive.

Erection: do not start erection until the mill reports for the shapes on that sequence are in the file.