

Division 07 Vapor Barrier

Practice file: Cedarline Training Hall, job SYNTH-HALL-01.

Original text. Not a real project and not a platform export.

Section 07 26 00. Underslab vapor barrier for the practice hall.

Product: 10 mil polyolefin sheet. The materials table lists it as SKU VB-10.

Laps: 6 inches minimum. Tape seams with the tape named in submittal SB-21.

Penetrations: boot and tape every pipe. A cut sheet without a boot is not finished.

Submittal SB-21 is revise and resubmit. The missing pages are the seam tape data sheet and the penetration detail.

Until SB-21 is accepted, this product sheet is information only. It is not an approval to place the slab.

Protection: do not drive equipment on the sheet. Patch cuts before any later work covers them.

Related concrete rules are in Division 03. Related review status is in the submittal log.